

UTAH OIL AND GAS CONSERVATION COMMISSION

REMARKS: WELL LOG _____ ELECTRIC LOGS _____ X WATER SANDS _____ LOCATION INSPECTED _____ SUB. REPORT/abd. _____

970730 Location abandoned eff. 7.28.97

DATE FILED JUNE 2, 1995

LAND: FEE & PATENTED

STATE LEASE NO.

PUBLIC LEASE NO.

INDIAN 14-20-H62-

DRILLING APPROVED: JULY 10, 1995

4418

SPUDDED IN:

COMPLETED: 7.28.97 LA PUT TO PRODUCING:

INITIAL PRODUCTION:

GRAVITY A.P.I.

GOR:

PRODUCING ZONES:

TOTAL DEPTH:

WELL ELEVATION:

DATE ABANDONED: JULY 28, 1997 LA'D

FIELD: UNDESIGNATED FIELD

UNIT: NA

COUNTY: UINTAH

WELL NO. UTE TRIBAL 21-7-F

API NO. 43-047-32691

LOCATION 2132' FNL FT. FROM (N) (S) LINE, 1966' FWL

FT. FROM (E) (W) LINE. SE NW

1/4 - 1/4 SEC. 21

TWP.

RGE.

SEC.

OPERATOR

TWP.

RGE.

SEC.

OPERATOR

4S

1E

21

SNYDER OIL CORPORATION

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

5. LEASE DESIGNATION AND SERIAL NO.

14-20-H62-4418

6. IF INDIAN, ALLOTTEE OR TRIBE NAME

Utah and Ouray Ute

7. UNIT AGREEMENT NAME

Not Applicable

8. FARM OR LEASE NAME WELL NO

Ute Tribal 21-7-F

9. API WELL NO.

10. FIELD AND POOL OR WILDCAT

Unnamed

11. SEC. T, R., M., OR BLK.
AND SURVEY OR AREA

SE 1/4 NW 1/4
Section 21, T4S, R1E

12. County

Utah

13. STATE

Utah

APPLICATION FOR PERMIT TO DRILL, DEEPEN, OR PLUG BACK

1a. TYPE OF WORK

DRILL ☒ DEEPEN ☐

1b. TYPE OF WELL

OIL
WELL ☒

GAS
WELL ☐

OTHER ☐

SINGLE
ZONE ☐

MULTIPLE
ZONE ☐

2. NAME OF OPERATOR

Snyder Oil Corporation

3. ADDRESS OF OPERATOR

1625 Broadway, Suite 2200; Denver, Colorado 80202

4. LOCATION OF WELL (Report location clearly and in accordance with any State requirements. *)

At Surface 2,132' FNL 1,966' FWL

At proposed Prod. Zone

Same as above

14. DISTANCE IN MILES AND DIRECTION FROM NEAREST TOWN OR POST OFFICE*

Approximately nine (13) miles south of Fort Duchesne, Utah

15. DISTANCE FROM PROPOSED* LOCATION TO NEAREST PROPERTY
OR LEASE LINE, FT. (Also to nearest drlg. unit line, if any)

1,966'

16. NO. OF ACRES IN LEASE

600'

17. NO. OF ACRES ASSIGNED TO THIS WELL

40

18. DISTANCE FROM PROPOSED LOCATION* TO NEAREST WELL,
DRILLING, COMPLETED, OR APPLIED FOR ON THIS LEASE, FT.

2,000'

19. PROPOSED DEPTH

6,623'

20. ROTARY OR CABLE TOOLS

Rotary

21. ELEVATIONS (Show whether DF, RT, GR, etc.)

5,162'

22. APPROX. DATE WORK WILL START*

July 07, 1995

23. PROPOSED CASING AND CEMENTING PROGRAM

SIZE OF HOLE	SIZE OF CASING	WEIGHT/FOOT	SETTING DEPTH	QUANTITY OF CEMENT
12-1/4"	8-5/8" J-55	J-55	24.0#	0-300'
7-7/8"	5-1/2" M-50	M-50	15.5#	6,707'
				225 SX circulated to surface*
				690 SX cement

* Cement volumes may change due to hole size as calculated from caliper log.

EIGHT-POINT RESOURCE PROTECTION PLAN ATTACHED

I hereby certify that Snyder Oil Corporation is authorized by the proper lease interest owners to conduct lease operations associated with this application for permit to drill the Ute Tribal 21-7-F, Federal Lease #14-20-H62-4418. Bond coverage pursuant to 43 CFR 3104 for lease activities is being provided by Snyder Oil Corporation Nationwide Bond #WY-2272, which will insure responsibility for compliance with all the terms and conditions of that portion of the lease associated with this application.

IN ABOVE SPACE DESCRIBE PROPOSED PROGRAM : If proposal is to deepen or plug back, give data on present productive zone and proposed new productive zone. If proposal is to drill or deepen directionally, give pertinent data on subsurface locations and measured and true vertical depths. Give blowout preventer program, if any.

24. SIGNED Paul W. McKinney TITLE Sr. Engineering Technician DATE May 25, 1995
FOR Jim McKinney

(This space for Federal or State office use)

PERMIT NO. 43-047-32691

APPROVAL DATE

Application approval does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon. CONDITIONS OF APPROVAL, IF ANY:

APPROVED BY


TITLE

DATE

*See Instructions On Reverse Side

Title 18 U.S.C. Section 1001, makes it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

APPROVED BY THE STATE
OF UTAH DIVISION OF
OIL, GAS, AND MINING
DATE: _____
BY: _____





T4S, R1E, U.S.B.&M.

SNYDER OIL CORP.

Well location, UTE TRIBAL #21-7-F, located as shown in the SW 1/4 NE 1/4 of Section 21, T4S, R1E, U.S.B.&M. Uintah County Utah.

SE NW
BASIS OF ELEVATION

SPOT ELEVATION AT THE SOUTHWEST CORNER OF SECTION 23, T4S, R1E, U.S.B.&M. TAKEN FROM THE UTELAND BUTTE QUADRANGLE, UTAH, UINAH COUNTY, 7.5 MINUTE QUAD. (TOPOGRAPHIC MAP) PUBLISHED BY THE UNITED STATES DEPARTMENT OF THE INTERIOR, GEOLOGICAL SURVEY. SAID ELEVATION IS MARKED AS BEING 5188 FEET.



CERTIFICATE

THIS IS TO CERTIFY THAT THE ABOVE PLAT WAS PREPARED FROM FIELD NOTES OF ACTUAL SURVEYS MADE BY ME OR UNDER MY SUPERVISION AND THAT THE SAME ARE TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF.

Robert L. King
REGISTERED LAND SURVEYOR
REGISTRATION NO. 161319
STATE OF UTAH

LEGEND:

- └ = 90° SYMBOL
- = PROPOSED WELL HEAD.
- ▲ = SECTION CORNERS LOCATED.

UINTAH ENGINEERING & LAND SURVEYING
85 SOUTH 200 EAST - VERNAL, UTAH 84078
(801) 789-1017

SCALE 1" = 1000'	DATE SURVEYED: 4-26-95	DATE DRAWN: 4-28-95
PARTY B.B. J.M. C.B.T.	REFERENCES G.L.O. PLAT	
WEATHER WARM	FILE SNYDER OIL CORP.	

SNYDER OIL CORPORATION
Lease #14-20-H62-4418, Ute Tribal 21-7-F
SW¼NE¼, Section 21, T4S, R1E
Uintah County, Utah

DRILLING PROGNOSIS

1. Estimated Tops of Important Geologic Markers

Uinta	Surface	Douglas Creek	5713'
Green River	2363'	Castle Peak	
6563'			
Top Thick Pay	5253'	Total Depth	6623'
Base Thick Pay	5328'		

2. Estimated Depths of Anticipated Water, Oil, Gas or Mineral Formations

Green River	2363'	Oil/Gas	(Possible)
Thick Pay	5253'	Oil/Gas	(Primary Objective)
Douglas Creek	5713'	Oil/Gas	(Possible)

Any shallow water zones encountered will be adequately protected and reported.
All potentially productive hydro-carbon zones will be cemented off.

3. Pressure Control Equipment - Schematic Attached

- A. Type:** Eleven (11) Inch Double Gate Hydraulic BOP with Eleven (11) Inch Annular Preventer and 3,000 psi wellhead.

The Blow-Out Preventer will be equipped as follows:

1. One (1) blind ram (above).
2. One (1) pipe ram (below).
3. Drilling spool with two (2) side outlets (choke side 3-inch minimum, kill side 2-inch minimum).
4. Kill line (2-inch minimum).
5. Two (2) kill line valves, one of which will be a check valve (2-inch minimum).
6. 3-inch (minimum) choke line.
7. Two (2) choke line valves (3-inch minimum).
8. Two (2) adjustable chokes.

3. **Pressure Control Equipment** - continued

9. Pressure gauge on choke manifold.
10. Upper kelly cock valve with handle available.
11. Full opening internal blowout preventer or drill pipe safety valve able to fit all connections.
12. Fill-up line above the uppermost preventer.

All BOP equipment will be rated for service in a sour gas environment.

B. Pressure Rating: 3,000 psi

C. Testing Procedure:

Annular Preventer

At a minimum, the Annular Preventer will be pressure tested to 50% of the rated working pressure for a period of ten (10) minutes or until provisions of the test are met, whichever is longer.

At a minimum, the above pressure test will be performed:

- 1) when the annular preventer is initially installed;
- 2) whenever any seal subject to test pressure is broken;
- 3) following related repairs; and
- 4) at thirty (30) day intervals.

In addition to the above, the annular preventer will be functionally operated at least weekly.

Blow-Out Preventer

At a minimum, the BOP, choke manifold, and related equipment will be pressure tested to the approved working pressure of the BOP stack (if isolated from the surface casing by a test plug) or to 70% of the internal yield strength of the surface casing (if the BOP is not isolated from the casing by a test plug). Pressure will be maintained for a period of at least ten (10) minutes or until the requirements of the test are met, whichever is longer.

At a minimum, the above pressure test will be performed:

- 1) when the BOP is initially installed;
- 2) whenever any seal subject to test pressure is broken;
- 3) following related repairs; and

3. Pressure Control Equipment - continued

- 4) at thirty (30) day intervals.

In addition to the above, the pipe and blind rams will be activated each trip, but not more than once each day.

All blowout preventer drills and tests will be recorded in the International Association of Drilling Contractors (IADC) driller's log.

D. Choke Manifold Equipment:

All choke lines will be straight lines unless turns use tee blocks or are targeted with running tees, and will be anchored to prevent whip and vibration.

E. Accumulator:

The accumulator will have sufficient capacity to open the hydraulically-controlled choke line valve (if so equipped), close all rams plus the annular preventer, and retain a minimum of 200 psi above precharge on the closing manifold without the use of the closing unit pumps. The fluid reservoir capacity will be double the accumulator capacity and the fluid level will be maintained at the manufacturer's recommendations.

The BOP system will have two (2) independent power sources to close the preventers. Nitrogen bottles (3 minimum) will be one (1) of these independent power sources and will maintain a charge equal to the manufacturer's specifications.

The accumulator precharge pressure test will be conducted prior to connecting the closing unit to the BOP stack and at least once every six (6) months thereafter. The accumulator pressure will be corrected if the measured precharge pressure is found to be above or below the maximum or minimum limits specified in *Onshore Oil & Gas Order Number 2*.

F. Special Drilling Operations:

In addition to the equipment already specified in Items A through E, above, the following equipment will be in place and operational during air/gas drilling:

1. Properly lubricated and maintained rotating head.
2. Spark arresters on engines or water cooled exhaust.
3. Bloopie line discharge 100 feet from well bore and securely anchored.

4. Straight run on blooie line.

F. Special Drilling Operations - continued

5. Deduster equipment (not required for aerated water system).
6. All cuttings and circulating medium(s) shall be directed into a reserve or blooie pit.
7. Float valve above bit.
8. Automatic igniter or continuous pilot light on the blooie line (not required for aerated water system).
9. Compressors located in the opposite direction from the blooie line and at a minimum of 100 feet from the well bore.
10. Mud circulating equipment, water, and mud materials (does not have to be pre-mixed) sufficient to maintain the capacity of the hole and circulating tanks or pits.

G. Miscellaneous Information:

The Blow-Out Preventer and related pressure control equipment will be installed, tested and maintained in compliance with the specifications in and requirements of *Onshore Oil & Gas Order Number 2*.

The choke manifold and BOP extension rods with hand wheels will be located outside the rig sub-structure. The hydraulic BOP closing unit will be located at least twenty-five (25) feet from the well head but readily accessible to the driller. Exact locations and configurations of the hydraulic BOP closing unit will depend upon the particular rig contracted to drill the Ute Tribal 21-7-F.

A flare line will be installed after the choke manifold, extending 125 feet (minimum) from the center of the drill hole to a separate flare pit.

4. The Proposed Casing and Cementing Program

A. Casing Program: All New

	<u>Hole Size</u>	<u>Casing Size</u>	<u>Wt./Ft.</u>	<u>Grade</u>	<u>Joint</u>	<u>Depth Set</u>
	12-1/4"	8-5/8"	24.0#	J-55		ST&C 0-
300'						
	7-7/8"	5-1/2"	15.5#	M-50		LT&C
0-6550'						

The surface casing will have centralizers on the bottom three (3) joints of casing, with a minimum of one (1) centralizer per joint starting with the shoe joint.

A. Casing Program - continued

Casing string(s) will be pressure tested to 0.22 psi/foot of casing string length or 1500 psi, whichever is greater (not to exceed 70% of the internal yield strength of the casing), after cementing and prior to drilling out from under the casing shoe.

The 5-1/2" production string has been designed for service in sour gas environments.

B. Cementing Program:

Surface Conductor - Set with approximately five (5) cubic yards (yd³) of Redi-Mix cement, circulated back to surface.

Surface Casing - Set with approximately 225 sx of Class "G" cement + additives, circulated back to surface.

Production Casing - Lead with approximately 345 sx of Pacesetter "Light" cement + additives.

Tail with approximately 330 sx of 50/50 Poz-Mix cement + additives.

A sufficient quantity of tail cement will be utilized to achieve full coverage across the upper Green River Formation. Estimated top of cement \approx 2087'.

The above cement volumes are approximate and were calculated under the assumption that a gauge hole will be achieved. Actual cement volumes may vary due to variations in the actual hole size and will be determined by running a caliper log on the drilled hole.

All waiting on cement (WOC) times will be adequate to achieve a minimum of 500 psi compressive strength at the casing shoe prior to drilling out.

5. Mud Program - Visual Monitoring

<u>Interval</u>	<u>Type</u>	<u>Weight</u>	<u>Viscosity</u>	<u>Fluid Loss</u>
0- 3000'	Fresh Wtr/Gel	8.2- 9.2	28-34	No Control
3000'-6707'	2% KCL Wtr/Gel	9.2- 9.8	30-45	15 + 25 cc's

¹ The initial drilling fluids system will consist of fresh water with bentonite gel for viscosity as needed for as long and/or as deep as possible (approximately 3000'). Should hole conditions deteriorate prior to reaching total depth, an

5. Mud Program - Visual Monitoring - continued

mud alternative drilling fluids system would be utilized consisting of a KCL/gel (with 2% KCL water as the base fluid).

Sufficient mud material(s) to maintain mud properties, control lost circulation and contain a blowout will be available at the well site during drilling operations.

No chromate additives will be used in the mud system on Federal or Indian lands without prior approval of the Bureau of Indian Affairs in order to ensure adequate protection of fresh water aquifers.

5. Mud Program - Continued

Hazardous substances specifically listed by the Environmental Protection Agency as a hazardous waste or demonstrating a characteristic of a hazardous waste will not be used in drilling, testing or completion operations.

6. Evaluation Program

Logs: FDC/CNL/SP/GR¹ - from 6623' to 3500'
Micro-SFL - from 6623' to 300'

¹ Pull Gamma Ray to surface.

DST's: None anticipated.

Cores: None anticipated.

The proposed Evaluation Program may change at the discretion of the well site geologist, with prior approval from the Authorized Officer, Bureau of Indian Affairs.

Stimulation: No stimulation or frac treatment has been formulated for this test at this time. The drill site, as approved, will be of sufficient size to accommodate all completion activities.

Whether the well is completed as a dry hole or as a producer, *Well Completion and Recompletion Report and Log* (Form #3160-4) will be submitted to the Vernal District Office not later than thirty (30) days after the

completion of the well or after completion of operations being performed, in accordance with 43 CFR 3164.

6. Evaluation Program - continued

Two (2) copies of all logs, core descriptions, core analyses, well test data, geologic summaries, sample description, and all other surveys or data obtained and compiled during the drilling, workover, and/or completion operations, will be filed with Form #3160-4. Samples (cuttings, fluids, and/or gases) will be submitted when requested by the Authorized Officer, Vernal District Office, Bureau of Land Management, 170 South 500 East, Vernal, Utah 84078, Telephone: (801) 789-1362.

7. Abnormal Conditions

No abnormal temperatures or pressures are anticipated. Hydrogen Sulfide (H₂S) may be encountered at approximately 5,400' and safety equipment will be in operation at 4,900'. A Hydrogen Sulfide (H₂S) Contingency Safety Plan is being prepared by an independent H₂S Safety Company and will be submitted under separate cover.

Maximum anticipated bottom hole pressure equals approximately 3,312 psi (calculated at 0.50 psi/ft of hole) and maximum anticipated surface pressure equals approximately 1,855 psi (bottom hole pressure minus the pressure of a partially evacuated hole calculated at 0.22 psi/foot of hole).

8. Anticipated Starting Dates and Notification of Operations

A. Anticipated Starting Dates:

Anticipated Commencement Date	July 07 , 1995
Drilling Days	Approximately 8 Days
Completion Days	Approximately 7 days

B. Notification of Operations:

Vernal District Office, Bureau of Land Management
Address : 170 South 500 East; Vernal, Utah 84078
Phone: (801) 789-1362
Fax: (801) 789-3634

In the event after-hours approvals are necessary, please contact one of the following individuals:

B. Notification of Operations - continued

<u>Contact Title</u>	<u>Contact Name</u>	<u>Home Phone</u>
Petroleum Engineer	Wayne Bankert	(801) 789-4470
Petroleum Engineer	Ed Forsman	(801) 789-7077

The Vernal District Office, Bureau of Land Management will be notified at least twenty-four (24) hours **PRIOR** to the commencement of the following activities:

1. Spudding of the well. This oral report will be followed up with a *Sundry Notice* (Form 3160-5);
2. initiating pressure tests of the blow-out preventer and related equipment;
3. running casing and cementing of ALL casing strings.

All lease and/or unit operations are to be conducted in such a manner that full compliance is made with the applicable laws, regulations (43 CFR, Part 3160), and this approved *Application for Permit to Drill*. The operator is considered fully responsible for the actions of his subcontractors. A copy of the approved

and *Application for Permit to Drill* must be on location during construction, drilling completion operations. The following items are emphasized:

DRILLING/PRODUCING OPERATING STANDARDS

There shall be no deviation from the proposed drilling and/or workover program as approved. Safe drilling and operating practices must be observed.

All wells, whether drilling, producing, suspended or abandoned shall be identified in accordance with 43 CFR 3162.6. There shall be a sign or marker with the name of the operator, the lease serial number, the well number and the surveyed description of the well.

Any changes in operations must have prior approval from the Authorized Officer (AO), Vernal District Office, Bureau of Land Management.

Pressure tests are required before drilling out from under all casing strings set and cemented in place. Blowout preventer controls will remain in use until the well is either completed or abandoned. Preventers will be inspected and operated at least daily to insure good mechanical working order, and this

B. Notification of Operations - continued

be inspection will be recorded on the daily drilling report. All BOP tests must be recorded in the daily drilling report.

NOTIFY RESOURCE AREA PETROLEUM ENGINEER AT LEAST TWENTY-FOUR (24) HOURS IN ADVANCE OF PRESSURE TESTS.

In accordance with *Onshore Oil & Gas Order Number 1*, this well will be reported on MMS Form #3160-6, *Monthly Report of Operations and Production*, starting with the month in which operations commence and continuing each month until the well is physically plugged and abandoned. This report will be filed directly with the Royalty Management Program, Minerals Management Service, P.O. Box 17110, Denver, Colorado 80217.

All undesirable events (fires, accidents, blowouts, spills, discharges) as specified in NTL-3A will be reported to the Vernal District Office. Major events will be reported verbally within twenty-four (24) hours and will be followed with a written report within fifteen (15) days. "Other than Major Events" will be reported in writing within fifteen (15) days. "Minor Events" will be reported on the *Monthly Report of Operations and Production* (Form #3160-6)

the No well abandonment operations will be commenced without the prior approval of the Authorized Officer. In the case of newly-drilled dry holes or failures, and in emergency situations, oral approval will be obtained from the Area Petroleum Engineer.

A *Notice of Intention to Abandon* (Form #3160-5) will be filed with the Authorized Officer within fifteen (15) days following the granting of oral approval to plug and abandon.

Upon completion of approved plugging, a regulation marker will be erected in accordance with 43 CFR 3162.6. The following information will be permanently placed on the marker with a plate, cap, or beaded-on with a welding torch: Company Name, Well Name and Number, Location by Quarter/Quarter, Section, Township, Range, and the Federal Lease Number.

A *Subsequent Report of Abandonment* (Form #3160-5) will be submitted within thirty (30) days following the actual plugging of the well bore. This report will indicate where plugs were placed and the current status of surface restoration operations. If surface restoration has not been completed at that time, a follow-up report on Form #3160-5 will be filed when all surface restoration work has been completed and the location is considered ready for final inspection.

B. Notification of Operations - continued

Pursuant to NTL-4A, lessees and operators are authorized to vent/flare gas during initial well evaluation tests, not exceeding a period of thirty (30) days or the production of fifty (50) MMCF of gas, whichever occurs first. An application must be filed with the Authorized Officer, and approval received, for any venting/flaring of gas beyond the initial thirty (30) day or otherwise authorized test period.

Not later than the 5th business day after any well begins production on which royalty is due anywhere on a lease site or allocated to a lease site, or resumes production in the case of a well which has been off production for more than ninety (90) days, the operator shall notify the Authorized Officer by letter or "*Sundry Notice*", of the date on which such production has begun or resumed. The notification shall provide as a minimum, the following informational items:

- a. Operator name, address, and telephone number
- b. Well name and number
- c. Well location " $\frac{1}{4}$, $\frac{1}{4}$, Section, Township, Range, P.M."
- d. Date well was placed in a producing status
- e. The nature of the wells production, i.e.: crude oil casing gas, or natural gas and entrained liquid hydrocarbons.
- f. The OCS, Federal or Indian lease prefix and number on which the well is located. Otherwise, the non-Federal or non-Indian land category, ie.: state or private.

Within sixty (60) days following construction of a new tank battery, a site facility diagram of the battery showing actual conditions and piping must be submitted to the Authorized Officer. Facility diagrams shall be filed within sixty (60) days after existing facilities are modified. For complete information as to what is required on these diagrams, please refer to 43 CFR 3162.7-4(d).

Pursuant to *Onshore Oil & Gas Order Number 1*, lessees and operators have the responsibility to see that their exploration, development, production, and construction operations are conducted in such a manner which conforms with

applicable federal laws and regulations and with state and local laws and regulations to the extent that such State and local laws are applicable to operations on Federal and Indian lands.

SNYDER OIL CORPORATION
Tribal Lease #14-20-H62-4651, Ute Tribal 21-7-F
SW¼NE¼, Section 21, T4S, R1E
Uintah County, Utah

MULTI-POINT SURFACE USE AND OPERATIONS PLAN
--

1. Existing Roads - Refer to Maps "A" and "B" (shown in ORANGE)

- A. The proposed well site is staked and four (4) 200-foot reference stakes are present.
- B. To reach the location from the city of Vernal, Utah; proceed generally west to Ft. Duchesne approximately 15 miles on U.S. Highway 40 (a paved U.S. Highway); thence south approximately 6.4 miles on an existing paved road (a paved Uintah County road) to the intersection of this road and an existing road to the west; turn left and proceed in a southerly direction approximately 6.4 miles on an existing Uintah County road, then generally west approximately 1.5 miles on an existing, upgraded oil field road and follow stakes to the Ute Tribal 21-7-F.
- C. Access roads - refer to Maps "A" and "B".
- D. Access roads within a one (1) mile radius - refer to Map "B".
- E. The existing roads will be maintained in the same or better condition as existed prior to the commencement of operations and said maintenance will continue until final abandonment and reclamation of the Ute Tribal 21-7-F well location.

2. Planned Access Roads - Refer to Map "B" (shown in GREEN)

Approximately thirty (3,168) feet of new road construction will be required for access to the proposed Ute Tribal 21-7-F well location from the Ute Tribal 21-7-F well pad. **Because the 21-7-F location occurs within Sclero Cactus habitat, SOCO agrees to provide a BIA approved botanist on location during the road and pad building phase of this project, so as to minimize the impact on cactus populations.**

- A. Width - maximum thirty (30) foot overall right-of-way with an eighteen (18) foot running surface, crowned and ditched for drilling and completion operations.

2. **Planned Access Roads** - continued

- B. Construction standard - the proposed access road will be constructed in accordance with roading guidelines established for oil & gas exploration and development activities as referenced in the joint BLM/USFS publication:

Surface Operating Standards for Oil and Gas Exploration and Development, Third Edition.

The access road will be designed and constructed to meet the standards of the anticipated traffic flow and all-weather requirements. Construction will include ditching, draining, graveling, crowning, and capping the roadbed as necessary to provide a well constructed and safe roadway.

Prior to construction/upgrading, the roadway shall be cleared of any snow cover and allowed to dry completely.

Traveling off of the thirty (30) foot right-of-way will not be allowed.

Drainage crossings shall be of the typical dry creek drainage crossing type. Crossings shall be designed so they will not cause siltation or the accumulation of debris in the drainage crossing nor shall the drainages be blocked by the roadbed. Erosion of drainage ditches by runoff water shall be prevented by diverting water off at a frequent intervals by means of cutouts.

Upgrading shall not be allowed during muddy conditions.

Should mud holes develop, they shall be filled in and detours around them avoided.

- C. Maximum grade - 3%.
- D. Turnouts - turnouts will be constructed along the access road route as necessary or required to allow for the safe passage of traffic. None anticipated for this short segment of new access road.
- E. Drainage design - the access road will be upgraded and maintained as necessary to prevent soil erosion and accommodate all-weather traffic. The proposed road will be crowned and ditched with water turnouts installed as necessary to provide for proper drainage along the access road route.
- F. Culverts, cuts and fills - no culverts will be required along the access road route. There are no major cuts and/or fills on/along the proposed access road route.

- G. Surfacing material - any construction materials which may be required for surfacing of the access road will be purchased from a local contractor having a

2. Planned Access Roads - continued

permitted source of materials within the general area, if required by the Authorized Officer, Bureau of Land Management.

- H. Gates, cattle guards or fence cuts - no gates, cattle guards or fence cuts will be required on/along the proposed access road route.
- I. Road maintenance - during both the drilling and production phase of operations, the road surface and shoulders will be kept in a safe and useable condition and will be maintained in accordance with the original construction standards.

All drainage ditches will be kept clear and free-flowing, and will also be maintained in accordance with the original construction standards.

The access road right-of-way will be kept free of trash during all operations.

- J. The proposed access road route has been centerline staked.

3. Location of Existing Wells Within a One-Mile Radius - Please Refer to Map "C".

- A. Water wells - NE $\frac{1}{4}$ NE $\frac{1}{4}$, Section 21, T4S, R1E.
- B. Abandoned wells - none known
- C. Temporarily abandoned wells - none known.
- D. Disposal wells - none known.
- E. Drilling wells - none known.
- F. Producing wells - NE $\frac{1}{4}$ NE $\frac{1}{4}$, Section 21, T4S, R1E.
NENW $\frac{1}{4}$ NE $\frac{1}{4}$, Section 21, T4S, R1E.
SWSE $\frac{1}{4}$ NE $\frac{1}{4}$, Section 21, T4S, R1E.
NESW $\frac{1}{4}$ NE $\frac{1}{4}$, Section 21, T4S, R1E.
NWNW $\frac{1}{4}$ NW $\frac{1}{4}$, Section 22, T4S, R1E.
NWSW $\frac{1}{4}$ NW $\frac{1}{4}$, Section 22, T4S, R1E.
- G. Shut-in wells - none known.
- H. Injection wells - none known.
- I. Monitoring wells - none known.

4. Location of Existing and/or Proposed Facilities Owned By Snyder Oil Corporation Within a One (1) Mile Radius

3. Location of Existing Wells Within a One-Mile Radius - Continued

A. Existing

1. Tank batteries - NE $\frac{1}{4}$ NE $\frac{1}{4}$, Section 21, T4S, R1E.
NENW $\frac{1}{4}$ NE $\frac{1}{4}$, Section 21, T4S, R1E.
NESW $\frac{1}{4}$ NE $\frac{1}{4}$, Section 21, T4S, R1E.
NWNW $\frac{1}{4}$ NW $\frac{1}{4}$, Section 22, T4S, R1E.
NWSW $\frac{1}{4}$ NW $\frac{1}{4}$, Section 22, T4S, R1E.
2. Production facilities - NE $\frac{1}{4}$ NE $\frac{1}{4}$, Section 21, T4S, R1E.
NENW $\frac{1}{4}$ NE $\frac{1}{4}$, Section 21, T4S, R1E.
SWSE $\frac{1}{4}$ NE $\frac{1}{4}$, Section 21, T4S, R1E.
NESW $\frac{1}{4}$ NE $\frac{1}{4}$, Section 21, T4S, R1E.
NWNW $\frac{1}{4}$ NW $\frac{1}{4}$, Section 22, T4S, R1E.
NWSW $\frac{1}{4}$ NW $\frac{1}{4}$, Section 22, T4S, R1E.
3. Oil gathering lines - none known.
4. Gas gathering lines - none known.

B. New Facilities Contemplated

1. All production facilities will be located on the disturbed portion of the well pad and at a minimum of twenty (20) feet from the toe of the back slope or top of the fill slope.
2. Should drilling result in the establishment of commercial production from the Ute Tribal 21-7-F well location, production facilities will require an area approximately 250' X 140'. ***Also, production from the 21-7-F well will be commingled with production from the 21-7-F well in a common battery located either on the 21-5-C or 21-7-F pad.***

A diagram showing the proposed production facility layout will be submitted to the Authorized Officer via "Sundry Notice" (Form 3160-5) for approval **PRIOR** to commencement of installation operations.

3. Production facilities will be accommodated on the disturbed portion of the well pad. Construction materials needed for installation of the production facilities will be obtained from the site; any additional materials needed will be purchased from a local supplier having a permitted source of materials in the general area.

3. Location of Existing Wells Within a One-Mile Radius - Continued

4. All permanent [on-site for six (6) months or longer] above-the-ground structures constructed or installed on the well location (including pumping units, tank batteries, etc.) will be painted a flat, non-reflective, earthtone color to match one of the standard environmental colors, as determined by the Five (5) State Rocky Mountain Interagency Committee.

The required paint color is Carlsbad Canyon, Munsell standard color number 2.5Y 6/2.

C. The production (emergency) pit will be fenced "*sheep-tight*" with woven wire mesh having two (2) top strands of barbed wire held in place by metal side posts and wooden corner "H" braces in order to protect livestock and wildlife (refer to Item 9F, page's 9 and 10).

D. During drilling and subsequent operations, all equipment and vehicles will be confined to the access road and any additional areas which may be specified in the approved Application for Permit to Drill.

E. Reclamation of disturbed areas no longer needed for operations will be accomplished by grading, leveling and seeding as recommended by the Authorized Officer, Bureau of Land Management.

5. Location and Type of Water Supply

- A. Fresh water for drilling will be obtained from the Duchesne River at a point located in the NW¼NW¼SW¼ of Section 23, Township 3 South, Range 1 East,(USBM) in Uintah County, Utah. Water will be diverted from th Duchesne

5. Location and Type of Water Supply - continued

River under a purchase agreement between Snyder Oil Corporation and the Uintah and Ouray Ute Indian Tribes.

In the event this source of water proves inadequate, fresh water for use in drilling and cementing operations would be obtained from the municipal water supply for the community of Fort Duchesne, Utah.

- B. Water will be transported via tank truck over existing roads from the point of diversion to the proposed Ute Tribal 21-7-F well location. No new road construction will be required on/along the proposed water haul route.

Access across any off-lease federal lands which may be crossed on/along the proposed water haul route will be secured under a separate right-of-way Grant/Special Use Permit to be obtained from the Uintah and Ouray Ute Indian Tribes and/or the Bureau of Indian Affairs (as applicable) prior to commencement of operations, if required.

- C. No water well will be drilled on this location.

6. Source of Construction Materials

- A. Any construction materials which may be required for surfacing of the drill pad will be obtained from a private contractor having a previously approved (private) source of materials within the general area.

Please refer to Item 2G (page 3) for information regarding any construction materials which may be required for on the access road.

- B. No construction materials will be taken from Federal or Indian lands without prior approval from the appropriate Surface Management Agency.
- C. If production is established, any construction materials which may be required for surfacing of the access road and/or installation of production facilities will be purchased from a local supplier having a permitted (private) source of materials within the general area.

- D. No new access roads for transportation of these construction materials will be required.

7. Methods of Handling Waste Materials

- A. Cuttings - the drilled cuttings will be deposited in the reserve pit.

7. Methods of Handling Waste Materials - Continued

- B. Drilling fluids - including any salts and/or chemicals utilized in the mud system will be contained in the reserve pit.

The reserve pit will be constructed so as not to leak, break, or allow discharge. Upon termination of drilling and completion operations, the liquid contents of the reserve pit will be removed and disposed of at an approved waste disposal facility within ninety (90) days after termination of drilling and completion activities.

In the event adverse weather conditions prevent removal of the fluids from the reserve pit within this time period, an extension may be granted by the Authorized Officer upon receipt of a written request from Snyder Oil Corporation.

- C. Produced fluids - liquids produced during completion operations will either be placed in test tanks on the well location (when a gel frac system is used) or into the reserve pit (when a foam frac system is used). Produced water will be confined to a lined pit (reserve pit) for a period not to exceed ninety (90) days after initial well completion.

During this ninety (90) day period, in accordance with *Onshore Oil & Gas Order Number 7*, an application for approval of a permanent disposal method and location, along with the required water analysis, shall be submitted to the Authorized Officer for review and approval as applicable. Failure to file an application within the time frame allowed will be considered as an incidence of noncompliance.

Any spills of oil, gas, salt water or any other potentially hazardous substance will be cleaned up and immediately removed to an approved disposal site.

- D. Sewage - portable, self-contained chemical toilets will be provided by Rocket Sanitation for human waste disposal. Upon completion of operations (or as required) the toilet holding tanks will be pumped and the contents thereof disposed of in an approved sewage disposal facility. Sewage disposal will be in strict accordance with applicable State of Utah rules and regulations regarding sewage treatment and disposal.

- E. Garbage and other waste material - all garbage and non-flammable waste materials will be contained in a self contained, portable dumpster or trash cage.

7. Methods of Handling Waste Materials - Continued

Upon completion of operations, or as needed, the accumulated trash will be hauled off-site to an approved sanitary landfill. No trash will be placed in the reserve pit.

- F. Immediately after removal of the drilling rig, all debris and other waste materials not contained in the trash cage will be cleaned up and removed from the well location. No potentially adverse materials or substances will be left on the location.

Any open pits will be fenced during the drilling operation and said fencing will be maintained until such time as the pits have been backfilled.

- G. Hazardous materials - Snyder Oil Corporation has no plans to utilize, store, transport or dispose of more than 10000 pounds any chemical or chemicals listed on or subject to the Environmental Protection Agency's *Consolidated List of Chemicals Subject to Reporting Under Title III of the Superfund Amendments and Reauthorization Act* (SARA) of 1986, or any extremely hazardous substances at or above the threshold planning quantities, as defined in 40 CFR 355, on the Ute Tribal 21-7-F lease.

8. Ancillary Facilities

None anticipated.

9. Wellsite Layout

- A. Figure #1 shows the drill site layout as staked. Cross sections have been drafted to visualize the planned cuts and fills across the proposed well location (refer to Figure #2).

A minimum of six (6) inches of topsoil will be stripped from the location (including areas of cut, fill, and/or subsoil storage) and stockpiled for future reclamation of the well site. Refer to Figure #1 for the location of the topsoil and subsoil stockpiles.

- B. Figure #1 is a diagram showing a typical rig layout. No permanent living facilities are planned on the Ute Tribal 21-7-F well location. There will be a maximum of three (3) trailers on location during drilling operations, which will serve as both office and housing for the mud logger, geologist and toolpusher.
- C. All equipment and vehicles will be confined to the approved areas in this Application for Permit to Drill (i.e., access road and well pad areas).

9. Wellsite Layout - Continued

- D. A diagram showing the proposed production facility layout will be submitted to the Authorized Officer via *Sundry Notice* (Form 3160-5) for approval prior to the commencement of installation operations. Please refer to Item 4B2 (page 4) for additional information in this regard.
- E. If porous subsoil materials (i.e., gravel, scoria, sand, faulted rock structures, etc.) are encountered during reserve pit construction, an impervious liner will be installed in order to prevent drilling water loss through seepage.

If required, this liner will have a permeability less than or equal to 1×10^{-7} cm/sec. The liner will be chemically compatible with all substances which may be put into the pit and will be installed so that it will not leak. Liners made of any man-made synthetic material will be of sufficient strength and thickness to withstand normal installation and pit use.

- F. Prior to the commencement of drilling operations, the reserve pit will be fenced "sheep tight" on the three (3) non-working sides according to the following minimum standards (if/as required by the Authorized Officer):
 - 1. 32-inch net wire shall be used with two (2) strands of barbed wire on top of (above) the net wire.
 - 2. The net wire shall be no more than four (4) inches above the ground. The first strand of barbed wire shall be \approx three (3) inches above the net wire. Total height of the fence shall be at least forty-two (42) inches.
 - 3. Corner posts shall be cemented and/or braced in such a manner to keep the fence tight at all times.
 - 4. Standard steel, wood, or pipe posts shall be used between the corner braces. The maximum distance between any two (2) posts shall be no greater than sixteen (16) feet.
 - 5. All wire shall be stretched, by using a stretching device, before it is attached to the corner posts.

The fourth (4th) side of the reserve pit will be fenced immediately upon removal of the drilling rig and the fencing will be maintained until the pit is backfilled.

- G. Any hydrocarbons on the pit will be removed as soon as possible after drilling operations are completed.

10. Plans for Reclamation of the Surface

- A. Rat and mouse holes will be backfilled and compacted from bottom to top immediately upon release of the completion rig from the location.
- B. If any oil is on the pits and is not immediately removed after operations cease, the pit containing the oil or other adverse substance(s) will be flagged overhead or covered with wire mesh to protect migrating waterfowl.
- C. Producing Operations:
1. Immediately upon well completion, the well location and surrounding area(s) will be cleared of all debris, materials, trash and junk not required for production.
 2. Immediately upon well completion, any hydrocarbons in the pit shall be removed in accordance with 43 CFR 3162.7-1.
 3. Before any dirt work to restore the location takes place, the reserve pit will be completely dry and all cans, barrels, pipe, etc. will be removed. All other waste and spoil materials will be disposed of immediately upon completion of drilling and completion activities.
 4. The reserve pit and that portion of the location and access road not needed for production facilities and/or operations will be reclaimed within ninety (90) days from the date of well completion, weather permitting.

be
the reserve

Prior to commencement of backfilling, the plastic or vinyl liner will be folded back into the pit. Fill material will then be pushed into the pit to completely cover both the pit and its contents.

- reclaimed
5. To prevent surface water (s) from standing (ponding) on the reserve pit area, final reclamation of the reserve pit

will result in the
"mounded" above the surrounding
feet) to allow the reclaimed pit surface area

ground surface over said pit being
ground surface (+/- three
to drain properly.

6. For production, the fill slopes will be reduced from a 1.5:1 slope to a 3:1 slope and the cut slopes will be reduced from a 1.5:1 slope to a 4:1 slope by pushing the fill material back up into the cut.
7. Upon completion of backfilling, leveling and recontouring, all disturbed surfaces (access road and well pad areas) will be scarified to a depth of

10. Plans for Reclamation of the Surface - continued

will
over the

one (1) foot and left with a rough surface. The stockpiled topsoil
then be evenly redistributed to a depth of six (6) inches
reclaimed area(s).

8. Prior to commencement of seeding operations, the seedbed will be prepared by disking on the contour to a depth of four (4) to six (6) inches, leaving no depressions that would trap water or form ponds.

All disturbed surfaces (including the access road and well pad areas) will be reseeded with a seed mixture to be recommended by the Authorized Officer, Bureau of Indian Affairs.

9. Seed will be drilled on the contour with a seed drill equipped with a depth regulator in order to ensure even depths of planting. Seed will be planted between one-quarter (1/4) to one-half (1/2) inches deep, with shrub seeds planted in rows separate from the grass seed, unless otherwise directed by the Authorized Officer, Bureau of Indian Affairs.

Where drilling is not possible (too steep or rocky), hand broadcast the seed at double the rate indicated above and rake or chain the area to cover the broadcast seed.

10. All seeding will be completed after September 15th and prior to ground frost. If the seeding is unsuccessful, subsequent seedings may be required.

the
satisfactory
achieved.

The first evaluation of growth will be made following completion of
first growing season. The seeding will be repeated until a
stand, as determined by the Authorized Officer, is

D. Dry Hole/Abandoned Well Location

1. On lands administered by the Bureau of Indian Affairs, abandoned well sites, roads, or other disturbed areas will be restored to near their original condition. This procedure will include:

- (a) re-establishing irrigation systems where applicable,
- (b) re-establishing soil conditions in irrigated fields in such a way as to ensure cultivation and harvesting of crops and,

D. Dry Hole/Abandoned Well Location - continued

- (c) ensuring revegetation of the disturbed areas to the specifications of the Uintah & Ouray Indian Tribes or The Bureau of Indian Affairs at the time of abandonment.

2. All disturbed surfaces will be recontoured to the approximate natural contours with reclamation of the well pad and access road to be performed as soon as practical after final abandonment.

Please refer to Item #10C3-4 (page #10) for specific reclamation of the reserve pit area.

3. Reseeding operations will be performed in the fall following completion of reclamations. Please refer to Item #10C9-10 for additional information regarding the reseeding operation.

11. Surface Ownership

The well location and proposed access road route are situated on surface lands owned by the Uintah & Ouray Ute Indian Tribes. These tribal lands are administered in trust for the Ute Indian Tribes by:

Bureau of Indian Affairs
Uintah & Ouray Agency
P. O. Box 130
Fort Duchesne, Utah 84026
Phone: (801) 722-2406

12. Other Information

A. General Description of the Project Area:

The project area is situated in the Uinta Basin section of the Colorado Plateaus physiographic province in an area of northeastern Utah which has undergone intensive natural gas development activities within the last few years. The overall area is characterized by moderately to severely eroded uplands located between the Duchesne River to the north and the Green River to the east. This area is classified as a "High Plains Steppe" (cold desert) and exhibits a sparse to moderate vegetation density which is typical of semi-arid areas at higher elevations (5000-6000').

Generally, local flora consists of native grasses such as salt grass, galleta grass, needle-and-threadgrass, Indian ricegrass; woody species such as shadscale,

A. General Description of the Project Area - continued

and horsebrush, black sagebrush, fringe sagebrush, big sagebrush, rabbitbrush, greasewood along the dry drainages.

Local fauna consists primarily of mule deer, mountain lions, coyotes, badgers, skunks, rabbits, raptors, and various smaller vertebrate and invertebrate species.

There are no known threatened or endangered species that would be affected by implementation of operations on the Ute Tribal 21-7-F well location.

B. Surface Use Activities:

The primary surface use is for livestock grazing.

C. Proximity of Water, Occupied Dwellings, Archaeological, Historical or Cultural Sites:

1. The closest source of permanent water is the Duchesne River, located approximately two (9) miles north of the proposed well location.
2. The closest occupied dwellings are located in the community of Fort Duchesne, Utah - approximately fifteen (15) miles to the north of the proposed well location.
3. A cultural resource clearance will be conducted before any construction activities begin on the proposed Ute Tribal 21-7-F well location. If, during operations, any archaeological or historical sites, or any object (s) of antiquity (subject to the Antiquities Act of June 8, 1906) are discovered, all operations which would affect such sites are to be suspended and the discovery reported promptly to the Bureau of Indian

Affairs.

Snyder Oil Corporation will be responsible for informing all persons associated with this project that they will be subject to prosecution for any archaeological, objects or site(s). damaging, altering, excavating or removing historical, or vertebrate fossil

If archaeological, historical or vertebrate fossil materials are discovered, Snyder Oil Corporation will suspend all operations that further disturb such materials and immediately contact the Authorized Officer.

C. Proximity of Water, Occupied Dwellings, Archaeological, Historical or Cultural Sites - continued

Operations will not resume until written authorization to proceed is issued by the Authorized Officer.

Within five (5) working days the Authorized Officer will evaluate the discovery and inform Snyder Oil Corporation of actions that will be necessary to prevent loss of significant cultural or scientific values.

Snyder Oil Corporation will be responsible for the cost of any mitigation required by the Authorized Officer. The Authorized Officer will provide technical and procedural guidelines for the conduct of mitigation. Upon verification from the Authorized Officer that the required mitigation has been completed, Snyder Oil Corporation will be allowed to resume operations.

D. Additional Requirements for Operations on Lands Administered by the Bureau of Indian Affairs:

1. If the surface rights are owned by the Ute Indian Tribe and mineral rights are owned by another entity, an approved right-of-way will be obtained from the Bureau of Indian Affairs (BIA) before the operator begins any construction activities. If the surface is owned by another entity and the mineral rights are owned by the Ute Indian Tribe, rights-of-way will be obtained from the other entity.

neat and of 2. All roads constructed by oil and gas operators on the Uintah & Ouray Indian Reservation will have appropriate signs. Signs will be sound construction and will state:

- (a) that the land is owned by the Uintah & Ouray Ute Indian Tribes,
- (b) the name of the operator,
- (c) that firearms are prohibited by all non-tribal members,
- (d) that permits must be obtained from the Bureau of Indian Affairs before cutting firewood or other timber products, and
- (e) only authorized personnel are permitted to use said road

D. Additional Requirements for Operations on Lands Administered by the Bureau of Indian Affairs - continued

lease description of section, township and 3. All well site locations on the Uintah & Ouray Ute Indian Reservation will have an appropriate sign indicating the name of the operator, the serial number, the well name and number, and the survey the well (either footages or the quarter-quarter, range).

construction 1362. 4. Snyder Oil Corporation shall contact both the Bureau of Indian Affairs (BIA) between 24 and 48 hours prior to commencement of activities. BIA: (801) 722-2406 BLM: (801) 789-

of Affairs, or 5. Snyder Oil Corporation will control noxious weeds along rights-of-way for roads, pipelines, well sites, or other applicable facilities. A list noxious weeds may be obtained from the Bureau of Indian Uintah County Extension Office.

obtained, pesticides or possible of noxious weeds. On lands administered by the Bureau of Indian Affairs, it is required that a "Pesticide Use Proposal" shall be submitted, and approval prior to the application of herbicides or other hazardous chemicals for the control

6. The BLM and BIA offices shall be notified upon site completion and prior to moving drilling tools onto the location.

13. Lessee's or Operator's Representative and Certification

Representative:

Snyder Oil Corporation
James M. McKinney, Sr. Engineering Technician
1625 Broadway, Suite 2200
Denver, Colorado 80202
Telephone: (303) 592-8500

- * Contact for any additional information which may be required for approval of this Application for Permit to Drill.

Certification:

All lease and/or unit operations will be conducted in such a manner that full compliance is made with all applicable laws, regulations (43 CFR 3100), *Onshore Oil & Gas Orders*, the approved plan of operations, and any applicable Notice to Lessees.

Certification - continued

Snyder Oil Corporation will be fully responsible for the actions of their subcontractors. A copy of these conditions will be furnished to their field representative(s) in order to ensure compliance.

The dirt contractor will be provided with a copy of the Surface Use Plan from the approved Application for Permit to Drill.

This drilling permit will be valid for a period of one (1) year from the date of approval. An extension period may be granted, if requested, prior to the expiration of the original approval period.

No location will be constructed or moved, no well will be plugged, and no drilling or work over equipment will be removed from a well to be placed in a suspended status without prior approval of the Authorized Officer. If operations are to be suspended, prior approval of the Authorized Officer will be obtained and notification given before resumption of operations.

I hereby certify that I, or persons under my direct supervision, have inspected the proposed drill site and access route; that I am familiar with the conditions which currently exist; that the statements made in this plan are, to the best of my knowledge, true and


correct; and that the work associated with the operations proposed herein will be performed by Snyder Oil Corporation, their contractors and subcontractors in conformity with this plan and the terms and conditions under which it is approved. This statement is subject to the provisions of 18 U.S.C. 1001 for the filing of a false statement.

May 25 1995 David W. McNamee
Date for James M. McKinney, Jr.

SNYDER OIL CORP.

LOCATION LAYOUT FOR

UTE TRIBAL #21-7-F
SECTION 21, T4S, R1E, U.S.B.&M.
2132' FNL 1966' FWL




SCALE: 1" = 50'
DATE: 4-29-95
Drawn By: C.B.T.

FIGURE #1

NOTE:

FLARE PIT IS TO BE LOCATED A MINIMUM OF 100' FROM THE WELL HEAD.



Elev. Ungraded Ground at Location Stake = **5088.6'**

Elev. Graded Ground at Location Stake = **5088.1'**


UINTAH ENGINEERING & LAND SURVEYING

85 So. 200 East • Vernal, Utah 84078 • (801) 788-1017






SNYDER OIL CORP.

TYPICAL CROSS SECTIONS FOR

UTE TRIBAL #21-7-F
SECTION 21, T4S, R1E, U.S.B.&M.
2132' FNL 1966' FWL



DATE: 4-29-95
Drawn By: C.B.T.



NOTE:

Topsoil should not be Stripped Below Finished Grade on Substructure Area.


FIGURE #2

APPROXIMATE YARDAGES

CUT
(12") Topsoil Stripping = 2,480 Cu. Yds.
Remaining Location = 7,310 Cu. Yds.
TOTAL CUT = 9,790 CU.YDS.
FILL = 2,050 CU.YDS.

EXCESS MATERIAL AFTER
5% COMPACTION = 7,630 Cu. Yds.
Topsoil & Pit Backfill
(1/2 Pit Vol.) = 2,950 Cu. Yds.
EXCESS CUT MATERIAL = 4,680 Cu. Yds.

UINTAH ENGINEERING & LAND SURVEYING
85 So. 200 East • Vernal, Utah 84078 • (801) 789-1017



TOPOGRAPHIC
MAP "A"

DATE: 5-1-95 C.B.T.



SNYDER OIL CORP.

UTE TRIBAL #21-7-F
SECTION 21, T4S, R1E, U.S.B.&M.
2132' FNL 1966' FWL

UTE TRIBAL #21-7-F
SECTION 21, T4S, R1E, U.S.B.&M.
2132' FNL 1966' FWL

WORKSHEET
APPLICATION FOR PERMIT TO DRILL

APD RECEIVED: 06/02/95

API NO. ASSIGNED: 43-047-32691

WELL NAME: UTE TRIBAL 21-7-F
OPERATOR: SNYDER OIL CORPORATION (N1305)

PROPOSED LOCATION:

SENW 21 - T04S - R01E
SURFACE: 2132-FNL-1966-FWL
BOTTOM: 2132-FNL-1966-FWL
UINTAH COUNTY
UNDESIGNATED FIELD (002)

LEASE TYPE: IND
LEASE NUMBER: 14-20-H62-4418

PROPOSED PRODUCING FORMATION: GRRV

INSPECT LOCATION BY: / /

TECH REVIEW	Initials	Date
Engineering		
Geology		
Surface		

RECEIVED AND/OR REVIEWED:

☒ Plat
☒ Bond: Federal ☒ State ☐ Fee ☐
(Number WY-2272)
☒ Potash (Y/N)
☒ Oil shale (Y/N)
☒ Water permit
(Number _____)
☒ RDCC Review (Y/N)
(Date: UTE TRIBE)



LOCATION AND SITING:

___ R649-2-3. Unit: _____
☒ R649-3-2. General.
___ R649-3-3. Exception.
___ Drilling Unit.
___ Board Cause no: _____
___ Date: _____

COMMENTS: _____

STIPULATIONS: _____

SNYDER OIL CORPORATION DEVELOPMENT DRILLING UINTAH COUNTY, NO SPACING



STATE OF UTAH
DIVISION OF OIL, GAS & MINING

DATE: 06/05/95



State of Utah
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

Michael O. Leavitt
Governor

Ted Stewart
Executive Director

James W. Carter
Division Director

355 West North Temple
3 Triad Center, Suite 350
Salt Lake City, Utah 84180-1203
801-538-5340
801-359-3940 (Fax)
801-538-5319 (TDD)

July 10, 1995

Snyder Oil Corporation
1625 Broadway, Suite 2200
Denver, Colorado 80202

Re: Ute Tribal #21-7-F Well, 2132' FNL, 1966' FWL, SE NW, Sec. 21, T. 4 S., R. 1 E.,
Uintah County, Utah

Gentlemen:

Pursuant to the provisions and requirements of Utah Code Ann. 40-6-1 et seq., Utah Administrative Code R649-3-1 et seq., and the attached Conditions of Approval, approval to drill the referenced well is granted.

This approval shall expire one year from the above date unless substantial and continuous operation is underway, or a request for extension is made prior to the expiration date. The API identification number assigned to this well is 43-047-32691.

Sincerely,


R. J. Firth
Associate Director

ldc

Enclosures

cc: Uintah County Assessor

Bureau of Land Management, Vernal District Office

WAPD



Operator: Snyder Oil Corporation

Well Name & Number: Ute Tribal #21-7-F

API Number: 43-047-32691

Lease: Indian 14-20-H62-4418

Location: SE NW Sec. 21 T. 4 S., R. 1 E.

Conditions of Approval

1. General

Compliance with the requirements of Utah Admin. R. 649-1 et seq., the Oil and Gas Conservation General Rules, and the applicable terms and provisions of the approved Application for Permit to Drill.

2. Notification Requirements


Notify the Division within 24 hours following spudding the well or commencing drilling operations. Contact Jimmie Thompson at (801)538-5340.

Notify the Division prior to commencing operations to plug and abandon the well. Contact Frank Matthews or Mike Hebertson at (801)538-5340.

3. Reporting Requirements

All required reports, forms and submittals shall be promptly filed with the Division, including but not limited to the Entity Action Form (Form 6), Report of Water Encountered During Drilling (Form 7), Weekly Progress Reports for drilling and completion operations, and Sundry Notices and Reports on Wells requesting approval of change of plans or other operational actions.

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT



Form approved.
Budget Bureau No. 1004-0136
Expires December 31, 1991

DOGNIA

APPLICATION FOR PERMIT TO DRILL, DEEPEN, OR PLUG BACK

1a. TYPE OF WORK
1b. TYPE OF WELL

DRILL ☒ DEEPEN ☐

OIL
WELL ☒

GAS WELL ☐ OTHER ☐ SINGLE ZONE ☐ MULTIPLE ZONE ☐

2. NAME OF OPERATOR
Snyder Oil Corporation

3. ADDRESS OF OPERATOR
1625 Broadway, Suite 2200; Denver, Colorado 80202

4. LOCATION OF WELL (Report location clearly and in accordance with any State requirements.)
At Surface 2,132' FNL 1,966' FWL

At proposed Prod. Zone

Same as above

14. DISTANCE IN MILES AND DIRECTION FROM NEAREST TOWN OR POST OFFICE*
Approximately nine (13) miles south of Fort Duchesne, Utah

15. DISTANCE FROM PROPOSED* LOCATION TO NEAREST PROPERTY OR LEASE LINE, FT. (Also to nearest drlg. unit line, if any)
1,966'

16. NO. OF ACRES IN LEASE
600'

17. NO. OF ACRES ASSIGNED TO THIS WELL
40

18. DISTANCE FROM PROPOSED LOCATION* TO NEAREST WELL, DRILLING, COMPLETED, OR APPLIED FOR ON THIS LEASE, FT.
2,000'

19. PROPOSED DEPTH
6,623'

20. ROTARY OR CABLE TOOLS
Rotary

21. ELEVATIONS (Show whether DF, RT, GR, etc.)
5,162'

22. APPROX. DATE WORK WILL START*
July 07, 1995

23. PROPOSED CASING AND CEMENTING PROGRAM

SIZE OF HOLE		SIZE OF CASING	WEIGHT/FOOT	SETTING DEPTH	QUANTITY OF CEMENT
12-1/4"	8-5/8" J-55	J-55	24.0#	0-300'	225 SX circulated to surface*
7-7/8"	5-1/2" M-50	M-50	15.5#	6,707'	690 SX cement

* Cement volumes may change due to hole size as calculated from caliper log.

EIGHT-POINT RESOURCE PROTECTION PLAN ATTACHED

I hereby certify that Snyder Oil Corporation is authorized by the proper lease interest owners to conduct lease operations associated with this application for permit to drill the Ute Tribal 21-7-F, Federal Lease #14-20-H62-4418. Bond coverage pursuant to 43 CFR 3104 for lease activities is being provided by Snyder Oil Corporation Nationwide Bond #WY-2272, which will insure responsibility for compliance with all the terms and conditions of that portion of the lease associated with this application.

RECEIVED
MAY 30 1995

IN ABOVE SPACE DESCRIBE PROPOSED PROGRAM : If proposal is to deepen or plug back, give data on present productive zone and proposed new productive zone. If proposal is to drill or deepen directionally, give pertinent data on subsurface locations and measured and true vertical depths. Give blowout preventer program, if any.

SIGNED Jim McKinney TITLE Sr. Engineering Technician DATE May 25, 1995
(This space for Federal or State office use)

PERMIT NO. _____ APPROVAL DATE _____
Application approval does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.

CONDITIONS OF APPROVAL, IF ANY:

APPROVED BY [Signature] TITLE ASSISTANT DISTRICT MANAGER MINING DATE JUL 10 1995

*See Instructions On Reverse Side

Title 18 U.S.C. Section 1001, makes it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

CONDITIONS OF APPROVAL ATTACHED
TO OPERATOR'S COPY

NOTICE OF APPROVAL

44080-510-160

CONDITIONS OF APPROVAL
APPLICATION FOR PERMIT TO DRILL

Company/Operator: Snyder Oil Corporation

Well Name & Number: Ute Tribal 21-7-F

API Number: 43-047-32691

Lease Number: 14-20-H62-4418

Location: ✓ SE NW Sec. 21 T. 04 S R. 1E

NOTIFICATION REQUIREMENTS

- Location Construction - at least forty-eight (48) hours prior to construction of location and access roads.
- Location Completion - prior to moving on the drilling rig.
- Spud Notice - at least twenty-four (24) hours prior to spudding the well.
- Casing String and Cementing - at least twenty-four (24) hours prior to running casing and cementing all casing strings.
- BOP and Related Equipment Tests - at least twenty-four (24) hours prior to initiating pressure tests.
- First Production Notice - within five (5) business days after new well begins, or production resumes after well has been off production for more than ninety (90) days.

For more specific details on notification requirements, please check the Conditions of Approval for Notice to Drill and Surface Use Program.

CONDITIONS OF APPROVAL FOR NOTICE TO DRILL

Approval of this application does not warrant or certify that the applicant holds legal or equitable title to those rights in the subject lease which would entitle the applicant to conduct operations thereon.

All lease and/or unit operations will be conducted in such a manner that full compliance is made with applicable laws, regulations (43 CFR 3100), Onshore Oil and Gas Orders, and the approved plan of operations. The operator is fully responsible for the actions of his subcontractors. A copy of these conditions will be furnished the field representative to insure compliance.

Be aware fire restrictions may be in effect when location is being constructed and/or when well is being drilled. Contact the appropriate Surface Management Agency for information.

A. DRILLING PROGRAM

1. Estimated Depth at Which Oil, Gas, Water, or Other Mineral Bearing Zones are Expected to be Encountered

Report ALL water shows and water-bearing sands to Tim Ingwell of this office. Copies of State of Utah form OGC-8-X are acceptable. If noticeable water flows are detected, submit samples to this office along with any water analyses conducted.

All usable water and prospectively valuable minerals (as described by BLM at onsite) encountered during drilling, will be recorded by depth and adequately protected. All oil and gas shows will be tested to determine commercial potential.

2. Pressure Control Equipment

The BOP and related equipment shall meet the minimum requirements of Onshore Oil and Gas Order No. 2 for equipment and testing requirements, procedures, etc., for a 3M system and individual components shall be operable as designed. Chart recorders shall be used for all pressure tests.

Test charts, with individual test results identified, shall be maintained on location while drilling and shall be made available to a BLM representative upon request.

If an air compressor is on location and is being utilized to provide air for the drilling medium while drilling, the special drilling requirements in Onshore Oil and Gas Order No. 2, regarding air or gas drilling shall be adhered to. If a mist system is being utilized then the requirement for a deduster shall be waived.

The Vernal District Office shall be notified, at least 24 hours prior to initiating the pressure tests, in order to have a BLM representative on location during pressure testing.

3. Casing Program and Auxiliary Equipment

Surface casing shall have centralizers on the bottom three joints, with a minimum of one centralizer per joint.

As a minimum, the usable water and oil shale resources shall be isolated and/or protected by having a cement top for the production casing at least 200 ft. above the base of the usable water zone, identified at ± 927 ft.. If gilsonite is encountered while drilling, it shall be isolated and/or protected via the cementing program.

The Vernal District Office shall be notified at least 24 hours prior to the running and cementing of all casing strings, in order to have a BLM representative on location while running and cementing all casing strings.

4. Mud Program and Circulating Medium

Hazardous substances specifically listed by the EPA as a hazardous waste or demonstrating a characteristic of a hazardous waste will not be used in drilling, testing, or completion operations.

No chromate additives will be used in the mud system on Federal and Indian lands without prior BLM approval to ensure adequate protection of fresh water aquifers.

5. Coring, Logging and Testing Program

Daily drilling and completion progress reports shall be submitted to this office on a weekly basis.

All Drill Stem tests (DST) shall be accomplished during daylight hours, unless specific approval to start during other hours is obtained from the AO. However, DSTs may be allowed to continue at night if the test was initiated during daylight hours and the rate of flow is stabilized and if adequate lighting is available (i.e., lighting which is adequate for visibility and vaporproof for safe operations). Packers can be released, but tripping should not begin before daylight unless prior approval is obtained from the AO.

A cement bond log (CBL) will be run from the production casing shoe to ± 727 ft. and shall be utilized to determine the bond quality for the production casing. Submit a field copy of the CBL to this office.

Whether the well is completed as a dry hole or as a producer, "Well Completion and Recompletion Report and Log" (Form 3160-4) will be submitted not later than 30 days after completion of the well or after completion of operations being performed, in accordance with 43 CFR 3164. Two copies of all logs, core descriptions, core analyses, well-test data, geologic summaries, sample description, and all other surveys or data obtained and compiled during the drilling, workover, and/or completion operations, will be filed with Form 3160-4. Samples (cuttings, fluids, and/or gases) will be submitted when requested by the AO.

6. Notifications of Operations

No location will be constructed or moved, no well will be plugged, and no drilling or workover equipment will be removed from a well to be placed in a suspended status without prior approval of the AO. If operations are to be suspended, prior approval of the AO will be obtained and notification given before resumption of operations.

The Vernal District Office shall be notified, during regular work hours (7:45 a.m.-4:30 p.m., Monday through Friday except holidays), at least 24 hours prior to spudding the well.

Operator shall report production data to MMS pursuant to 30 CFR 216.5 using form MMS/3160.

Immediate Report: Spills, blowouts, fires, leaks, accidents, or any other unusual occurrences shall be promptly reported in accordance with the requirements of NTL-3A or its revision.

If a replacement rig is contemplated for completion operations, a "Sundry Notice" (Form 3160-5) to that effect will be filed, for prior approval of the AO, and all conditions of this approved plan are applicable during all operations conducted with the replacement rig.

The date on which production is commenced or resumed will be construed for oil wells as the date on which liquid hydrocarbons are first sold or shipped from a temporary storage facility, such as a test tank, and for which a run ticket is required to be generated or, the date on which liquid hydrocarbons are first produced into a permanent storage facility, whichever first occurs; and, for gas wells as the date on which associated liquid hydrocarbons are first sold or shipped from a temporary storage facility, such as a test tank, and for which a run ticket is required to be generated or, the date on which gas is first measured through permanent metering facilities, whichever first occurs.

Should the well be successfully completed for production, the AO will be notified when the well is placed in a producing status. Such notification will be sent by telegram or other written communication, not later than five (5) days following the date on which the well is placed on production.

Gas produced from this well may not be vented or flared beyond an initial authorized test period of 30 days or 50 MMCF following its completion, whichever occurs first, without the prior written approval of the Authorized Officer. Should gas be vented or flared without approval beyond the authorized test period, the operator may be directed to shut-in the well until the gas can be captured or approval to continue venting or flaring as uneconomic is granted and the operator shall be required to compensate the lessor for that portion of the gas vented or flared without approval which is determined to have been avoidably lost.

A schematic facilities diagram as required by 43 CFR 3162.7-5 (b.9. d.) shall be submitted to the appropriate District Office within sixty (60) days of installation or first production, whichever occurs first. All site security regulations as specified in Onshore Oil & Gas Order No. 3 shall be adhered to. All product lines entering and leaving hydrocarbon storage tanks will be effectively sealed in accordance with 43 CFR 3162.7-5 (b. 4).

No well abandonment operations will be commenced without the prior approval of the AO. In the case of newly drilled dry holes or failures, and in emergency situations, oral approval will be obtained from the AO. A "Subsequent Report of Abandonment" Form 3160-5, will be filed with the AO within thirty (30) days following completion of the well for abandonment. This report will indicate where plugs were placed and the current status of surface restoration. Final abandonment will not be approved until the surface reclamation work required by the approved APD or approved abandonment notice has been completed to the satisfaction of the AO or his representative, or the appropriate Surface Managing Agency.

7. Other Information

All loading lines will be placed inside the berm surrounding the tank battery.

All off-lease storage, off-lease measurement, or commingling on-lease or off-lease will have prior written approval from the AO.

The oil and gas measurement facilities will be installed on the well location. The oil and gas meters will be calibrated in place prior to any deliveries. Tests for meter accuracy will be conducted following initial installation and at least quarterly thereafter. The AO will be provided with a date and time for the initial meter calibration and all future meter proving schedules. A copy of the meter calibration reports will be submitted to the Vernal District Office. All meter measurement facilities will conform with Onshore Oil & Gas Order No. 4 for liquid hydrocarbons and Onshore Oil & Gas Order No. 5 for natural gas measurement.

The use of materials under BLM jurisdiction will conform to 43 CFR 3610.2-3.

There will be no deviation from the proposed drilling and/or workover program without prior approval from the AO. Safe drilling and operating practices must be observed. All wells, whether drilling, producing, suspended, or abandoned will be identified in accordance with 43 CFR 3162.

"Sundry Notice and Report on Wells" (Form 3160-5) will be filed for approval for all changes of plans and other operations in accordance with 43 CFR 3162.3-2.

Section 102(b)(3) of the Federal Oil and Gas Royalty Management Act of 1982, as implemented by the applicable provisions of the operating regulations at Title 43 CFR 3162.4-1(c), requires that "not later than the 5th business day after any well begins production on which royalty is due anywhere on a lease site or allocated to a lease site, or resumes production in the case of a well which has been off production for more than 90 days, the operator shall notify the authorized officer by letter or sundry notice, Form 3160-5, or orally to be followed by a letter or sundry notice, of the date on which such production has begun or resumed."

If you fail to comply with this requirement in the manner and time allowed, you shall be liable for a civil penalty of up to \$10,000 per violation for each day such violation continues, not to exceed a maximum of 20 days. See Section 109(c)(3) of the Federal Oil and Gas Royalty Management Act of 1982 and the implementing regulations at Title 43 CFR 3162.4-1(b)(5)(ii).

APD approval is valid for a period of one (1) year from the signature date. An extension period may be granted, if requested, prior to the expiration of the original approval period.

In the event after-hours approval or notification is necessary, please contact one of the following individuals:

Wayne Bankert (801) 789-4170
Petroleum Engineer

Ed Forsman (801) 789-7077
Petroleum Engineer

BLM FAX Machine (801) 781-4410

EPA'S LIST OF NONEXEMPT EXPLORATION AND PRODUCTION WASTES

While the following wastes are nonexempt, they are not necessarily hazardous.

- Unused fracturing fluids or acids
- Gas plant cooling tower cleaning wastes
- Painting wastes
- Oil and gas service company wastes, such as empty drums, drum rinsate, vacuum truck rinsate, sandblast media, painting wastes, spent solvents, spilled chemicals, and waste acids
- Vacuum truck and drum rinsate from trucks and drums, transporting or containing nonexempt waste
- Refinery wastes
- Liquid and solid wastes generated by crude oil and tank bottom reclaimers
- Used equipment lubrication oils
- Waste compressor oil, filters, and blowdown
- Used hydraulic fluids
- Waste solvents
- Waste in transportation pipeline-related pits
- Caustic or acid cleaners
- Boiler cleaning wastes
- Boiler refractory bricks
- Incinerator ash
- Laboratory wastes
- Sanitary wastes
- Pesticide wastes
- Radioactive tracer wastes
- Drums, insulation and miscellaneous solids.

SURFACE USE PLAN OF OPERATION
Conditions of Approval (COA's)

1. All vehicular traffic, personnel movement, construction and restoration operations should be confined to the areas examined, as referenced in report, and to the existing roadways and/or evaluated access routes.
2. All recommendations of the Bureau of Indian Affairs, combined site specific Environmental Analysis (EA) report shall be strictly adhered, during and after construction.
3. All personnel should refrain from collecting artifacts and from disturbing any significant cultural resources in the area.
4. The personnel from the Ute Tribe Energy & Minerals Department should be consulted, should cultural remains from subsurface deposits be exposed during construction work.

Mitigation stipulations from the combined site specific Environmental Analysis.

1. Before the site is abandoned the company will be required to restore the well pad and access road to near their original state. The disturbed area will be reseeded with desirable perennial vegetation.

Although the road rights-of-way will be 30 feet wide, the graded area of the road will be limited in most places to 21 feet between the top of the cut and toe of the fill. Where deep cuts are required for road construction, or where intersections or sharp curves occur the road may be constructed wider than 21 feet so that large pieces of equipment will have enough room to make turns.

2. Noxious weeds will be controlled on all well sites and rights-of-way. If noxious weeds spread from the well sites or rights-of-way onto adjoining land, the company will also be responsible for their control.
3. The reserve pit will be lined with an impervious synthetic liner.
4. The synthetic liner will be bedded with fine textured earthen material which is free of rocks. Straw may be used in addition to the earthen material, but not in leu of it.

5. Use a metal or fiberglass tank in the place of an emergency pit for the production system.
6. Production water, oil, and other by-products will not be applied to roads or well pads for the control of dust or weeds. Indiscriminate dumping of oil field by-products on tribal lands will not be allowed.
7. To protect the Sclerocactus brevispinus a botanist will be hired by Snyder Oil Corporation to survey the road right-of-way. If the cacti is located within the right-of-way, slight modifications will be made in alignment of the road to protect the cacti. These modifications will not be made if the modifications cause excessive cost or hardship to the oil company.



United States Department of the Interior

BUREAU OF INDIAN AFFAIRS

UINTAH AND OURAY AGENCY
FORT DUCHESNE, UTAH 84026
(801) 722-2406

IN REPLY REFER TO:
Minerals & Mining Dept.
UIT 21-7-F

Snyder Oil Corporation
1625 Broadway, Suite 2200
Denver, CO 80202

Dear Sirs:

This is your authority to proceed with the following proposed on-lease wellsite, access road and pipeline right-of-way which is identified as a Mineral Access Agreement, in accordance with the Ute Tribe recommendations listed for the following location:

UTE TRIBAL #21-7-F, Section 21, SENW,
Township 4 South, Range 1 East, USBM

The Ute Tribe Energy & Minerals Department requires that Snyder adhere to the following criteria during all phases of construction activities, during and after:

1. All vehicle traffic, personnel movement, construction and restoration operations should be confined to the areas examined, as referenced in report and to the existing roadways and/or evaluated access routes.
2. All personnel should refrain from collecting artifacts and from disturbing any significant cultural resources in the area.
3. The personnel from Ute Tribe Energy & Minerals Department should be consulted should cultural remains from subsurface deposits be exposed during construction work.
4. All recommendations of the Bureau of Indian Affairs combined site specific environmental analysis (EA) should be strictly adhered..

Enclosed are two (2) approved Mineral Access Agreements for your files. Upon completion of construction, please submit in **triplicate**, the following documents:

- a. Affidavit of Completion of Construction
- b. "As Built" maps, with accompanying Certification of Right-of-way.

If you have any questions in regard to the above, please feel free to contact us at the above address and/or telephone number.

Sincerely,


Superintendent



United States Department of the Interior

BUREAU OF INDIAN AFFAIRS

UINTAH AND OURAY AGENCY

FORT DUCHESNE, UTAH 84026

(801) 722-2406 51/52/54

IN REPLY REFER TO:

Minerals and Mining

MINERAL ACCESS AGREEMENT ON INDIAN OWNED LANDS

Well No. 21-7-F

The purpose of this agreement is to regulate the surface development of Indian Lands which have been leased for oil and gas development. An approved agreement must be obtained prior to the commencement of any surface disturbing activity and will be in effect for the term of the lease and the agreed upon contractual provisions referenced therein, in not revoked under the terms in Item 4 of this agreement.

1. The authorized officer for the Bureau of Indian Affairs, in conjunction with the Indian Surface owner and Tribe hereby grants permission to:

Snyder Oil Corporation

To improve and/or construct and maintain a development corridor which may contain an access road, pipelines, powerlines, communication lines and well pads on the following trust land (reference lease number and legal description):

SE / NW Section 21 T4S R1E
Uintah Co. Utah

2. In consideration of the approval of this agreement, the above company agrees to adhere to all lease provisions, A.P.D. stipulations and regulations of the Secretary of the Interior now or hereafter in force relative to such leases.
3. The Company herewith submits an estimated surface damage fee in the amount of \$ _____, for _____ acres Pending Agency appraisal and the Affidavit of Completion.
4. This agreement will remain in effect unless revoked upon 30 days written notice by the Superintendent or the appropriate official, depending upon circumstances.
5. The permittee will submit a certified survey map of the proposed access road and/or well pad with this permit. The map must adhere to all specifications and requirements of the Branch of Minerals and Mining, Uintah and Ouray Agency, Bureau of Indian Affairs. Upon completion of construction, an Affidavit of Completion will be submitted by the company to certify that the construction completed was in accordance to the specifications certified to on the survey map accompanying this agreement.
6. The Company agrees to furnish a bond in the amount of \$ _____, or to utilize said company's existing Nationwide Oil and Gas Bond No. _____ to guarantee performance of this permit.
7. The Company agrees to contact immediately the Bureau of Indian Affairs (BIA) and the Bureau of Land Management (BLM), if cultural resources discovered during construction or anytime during the course of daily operations.
8. ADDITIONAL STIPULATIONS:

Signed on this 26 day of June, 1995.

WITNESS:

Larry Nance

G. M. Smith
AUTHORIZED AGENT

Snyder Oil Corporation
COMPANY NAME

P.O. Box 695

ADDRESS

Vernal, Utah

CITY/STATE

84078

ZIP CODE

APPROVED:

[Signature]
Superintendent

7/5/95
Date



United States Department of Interior

BUREAU OF INDIAN AFFAIRS

UINTAH AND OURAY AGENCY
FORT DUCHESNE, UTAH 84026
(801) 722-2406 51/52/54

IN REPLY REFER TO:

Minerals and Mining

MINERAL ACCESS AGREEMENT ON INDIAN OWNED LANDS

Well No. 21-7-F

The purpose of this agreement is to regulate the surface development of Indian Lands which have been leased for oil and gas development. An approved agreement must be obtained prior to the commencement of any surface disturbing activity and will be in effect for the term of the lease and all agreed upon contractual provisions referenced therein, in not revoked under the terms in Item 4 of this agreement.

1. The authorized officer for the Bureau of Indian Affairs, in conjunction with the Indian Surface owner and Tribe hereby grants permission to Snyder Oil Corporation

To improve and/or construct and maintain a development corridor which may contain an access road, pipelines, powerlines, communication lines and well pads on the following trust land (reference lease number and legal description):

SE 1/4 NW Section 21 T4S R1E
Uintah Co. Utah

2. In consideration of the approval of this agreement, the above company agrees to adhere to all lease provisions, A.P.D. stipulations and regulations of the Secretary of the Interior now or hereafter in force relative to such leases.
3. The Company herewith submits an estimated surface damage fee in the amount of \$ _____, for _____ acres Pending Agency appraisal and the Affidavit of Completion.
4. This agreement will remain in effect unless revoked upon 30 days written notice by the Superintendent or the appropriate official, depending upon circumstances.
5. The permittee will submit a certified survey map of the proposed access road and/or well pad with this permit. The map must adhere to all specifications and requirements of the Branch of Minerals and Mining, Uintah and Ouray Agency, Bureau of Indian Affairs. Upon completion of construction, an Affidavit of Completion will be submitted by the company to certify that the construction completed was in accordance to the specifications certified to on the survey map accompanying this agreement.
6. The Company agrees to furnish a bond in the amount of \$ _____, or to utilize said company's existing Nationwide Oil and Gas Bond No. _____ to guarantee performance of this permit.
7. The Company agrees to contact immediately the Bureau of Indian Affairs (BIA) and the Bureau of Land Management (BLM), if cultural resources discovered during construction or anytime during the course of daily operations.

8. ADDITIONAL STIPULATIONS:

Signed on this 26 day of June, 1995.

WITNESS: Larry Neme

J. M. Smith
AUTHORIZED AGENT
Snyder Oil Corporation
COMPANY NAME
P.O. Box 695
ADDRESS
Vernal, Utah 84078
CITY/STATE ZIP CODE

APPROVED:

[Signature]
Superintendent

7/5/95
Date

memorandum

DATE: July 5, 1995

REPLY TO
ATTN OF:

Superintendent, Uintah & Ouray Agency

SUBJECT:

Concurrence for Snyder Oil Corporation
Ute Tribal 21-7-F, SENW, Sec. 21, T4S, R1E

TO:

Bureau of Land Management, Vernal District Office
Attention: Division of Minerals and Mining


We recommend approval of the Application for Permit to Drill on the Subject well.

Based on available information received on 05/15/95, we have cleared the proposed location in the following areas of environmental impact.

YES <input checked="" type="checkbox"/>	NO <input type="checkbox"/>	Listed threatened or endangered species
YES <input checked="" type="checkbox"/>	NO <input type="checkbox"/>	Critical wildlife habitat
YES <input checked="" type="checkbox"/>	NO <input type="checkbox"/>	Archaeological or cultural resources
YES <input type="checkbox"/>	NO <input type="checkbox"/>	Air quality aspects (to be used only if project is in or adjacent to a class I area of attainment.)
YES <input type="checkbox"/>	NO <input type="checkbox"/>	Other (if necessary)

REMARKS: The Ute Tribe Energy & Minerals Department is recommending the following criteria to be adhered during all phases of construction activities.

1. All vehicular traffic, personnel movement, construction and restoration operations should be confined to the area examined, as referenced in report, and to the existing roadways and/or evaluated access routes.
2. All personnel should refrain from collecting artifacts and from disturbing any significant cultural resources in the area.
3. The personnel from the Ute Tribe Energy & Minerals Department should be consulted, should cultural remains from subsurface deposits be exposed during construction work.
4. All recommendations of the Bureau of Indian Affairs, combined site specific Environmental Analysis (EA) report shall be strictly adhered, during and after construction.



Attachment:

BIA Environmental Analysis (EA), dated June 7, 1995

**SITE SPECIFIC
ENVIRONMENTAL ANALYSIS**

1.0 PROPOSED ACTION

Snyder Oil Corporation is proposing to drill the Ute Tribal oil well #21-7-F, and construct 0.2 miles of access road.

2.0 ALTERNATIVE ACTIONS

- A. ALTERNATIVE CONSIDERED: The proposed action is the preferred alternative.
- B. NO ACTION: Under the no action alternative the proposed action would not be implemented.
- C. OTHER: NA

3.0 PERMITTEE/LOCATION

- A. Permittee- Snyder Oil Corporation
- B. Date-5-15-95
- C. Well number- Ute Tribble #21-7-F
- D. Right-of-way- Access road and pipeline R\W 0.2 miles
- E. Site location SENW, Section 21, T4S, R1E, USB&M.

4.0 SITE SPECIFIC SURVEY

A. SITE DESCRIPTION

- 1. Elevation (feet) 5089
- 2. Annual precipitation (inches)- 4 to 8
- 3. Topography - hills
- 4. Soil- The soil texture is (0 to 6") medium & fine textured with a gravel pavement, and has moderately slow water intake rate and permeability.

B. VEGETATION

- 1. Habitat type is semi-desert shrub.
- 2. Percent Ground Cover- 30% over the area of the pipeline r\w.
- 3. Vegetation consists of approximately 30% grasses, 20% scrubs, and 50% forbs. The main variety of grass is Galletta, Needle and thread, Indian ricegrass, Squirrel tail, and Cheat grass. Forbs are Mustard, Astragalus, Indian paint brush, and other annuals. Scrubs consist of

Nuttall saltbush, Sclerocactus brevispinus, Pricklypear, Black sage, Bud sage, Rabbit brush.

4. Observed Threatened & Endangered species: None.

5. The potential For Threatened & Endangered species is slight, but there is a short spined variety of Sclerocactus present within the project area. (Approximately 6.0 of the short spined cacti were located over the project area. Approximately 60% of the project area is estimated to be habitat for the short spined cacti. There is a preliminary proposal from the USFWS to add the plant to the list of T&E Plant species. According to Larry England of the USFWS, the plant is not presently protected under the T&E Species Act.

7. Observed Noxious Weeds: None

8. AFFECTED ENVIRONMENTAL

1. There are no surface damages as a result of the initial survey.

4.1 WILDLIFE

A. POTENTIAL SITE UTILIZATION

1. Big Game- There is minimal use by mule deer and antelope.

2. Small Game- There are cottontail rabbit and morning dove in the area and may use the site.

3. Raptor/Bird- Various species of raptors use this area for habitat. Raptors which are observed using the area are Golden eagles, Redtail hawk, & Kestrel. There are large cliffs and rock outcrops within a short distance of the proposed project. No nests are known to exist within 1/2 mile of the project area.

5. Non-Game Wildlife- Animal species which have been observed using this area are coyote, fox, badger, and various species of reptiles, and song birds.

6. Threatened & Endangered Species: Bald eagles migrate into the area along the Duchesne, Green Rivers, and Pariette draw during the winter months. They are not commonly observed in this area, but on occasion they may fly over the area.

4.2 PRESENT SITE USE

A. USAGE

	<u>acres</u>
Rangeland	2.73
Irrigable land	0
Woodland	0
Non-Irrigable land	2.73
Commercial timber	0
Floodplain	0
Wetland	0
Riparian	0
Other:	0

4.3 CULTURAL RESOURCES

A. CULTURAL SURVEY

The well site, and access road had a cultural resource survey performed by Carl Spath, Ph.D., Metcalf Archaeological Consultants, Inc.

5.0 ENVIRONMENTAL IMPACTS

A. SURFACE ALTERATIONS

	<u>acres</u>
1. Access road	0.73
2. Well site	2.00
3. Pipeline right-of-way	0
4. Total area disturbed	2.73

B. VEGETATION/LANDSCAPE

1. Production loss (AUM's)/year: 0.14
2. Permanent scar on landscape: Yes X No
3. Potential impacts to Threatened & Endangered species:
Yes No X (The area is habitat for a short
spined Sclerocactus. This plant is considered rare by
USFWS and may be listed on the T&E species list in the
future. At the present time it is not protected.)

C. SOIL/RANGE/WATERSHED

There will be an increase in wind and water erosion as a result of removing vegetation and exposing the soil from construction of the wellsite and access road. This will increase water runoff and the soil will remain exposed causing erosion to continue for the life of the well, and until the site is rehabilitated.

The site is located approximately 2.0 miles away from

the Pariette Draw which is a perennial streams. Therefore, if an accidental spill should occur at the wellsite it is not likely there would be point sources of water pollution from this project.

The area will have a closed production system. Produced water will be stored in closed tanks until it is either injected into injection wells, or hauled to approved disposal pits. Reserve pits containing well cuttings, clays, and additives for drilling are not considered hazardous. They will be buried at the well site.

The excess fluids left in the reserve pit after the well is drilled will be hauled to approved disposal pits. Loading the soil with salt or contamination of Pariette Draw from produced water will only occur when there are accidental spills. Therefore, the impact from produced water and oil by-products to the soil and water will be minimal.

The area is presently used as rangeland and permits have been issued by BIA for grazing livestock. This project will reduce livestock grazing by approximately 0.14 AUM/year.

The area is not used as irrigated cropland and a water right has not been designated for the area. Because of the topography and high salt content of the soil the area is not feasible for crop production.

D. WILDLIFE/THREATENED & ENDANGERED SPECIES

There will be a reduction of wildlife habitat and grazing for livestock. There will also be an increase in wildlife disturbance and poaching resulting from the additional traffic and people using the area. There may be an impacts to the short spined Sclerocactis species and its habitat.

6.0 MITIGATION STIPULATIONS

A. VEGETATION/LANDSCAPE

1. Before the site is abandoned the company will be required to restore the well pad, and access road to near their original state. The disturbed area will be reseeded with desirable perennial vegetation.

Although the road rights-of-way will be 30 feet wide, the graded area of the road will be limited in most places to 21 feet between the Top of the cut and toe of the fill. Where deep cuts are required for road construction, or

where intersections or sharp curves occur the road may be constructed wider than 21 feet so that large pieces of equipment will have enough room to make turns.

2. Noxious weeds will be controlled on all well sites and rights-of-way. If noxious weeds spread from the well sites or rights-of-way onto adjoining land, the company will also be responsible for their control.

B. SOILS/RANGE/WATERSHEDS

1. Soil erosion will be mitigated by reseeding all disturbed areas.
2. Approximately 17 rods of fence will be constructed around the reserve pit until it is back filled.
3. Salt and pollution loading of the soil and geological formations will be mitigated by requiring the oil company to:

- a. Lined reserve pits with impervious synthetic liners.
- b. Use a metal or fiberglass tank in the place of an emergency pit for the production system.

Reason(s): Pariette Draw and wildlife refuge is located approximately 2.0 miles downstream from the project.

- c. Production water, oil, and other by-products will not be applied to roads or well pads for the control of dust or weeds. Indiscriminate dumping of oil field by-products on tribal lands will not be allowed.
4. To protect the Sclerocactus brevispinus a botanist will be hired by Snider Oil Corp. to survey the road right-of-way. If the cacti is located within the right-of-way, slight modifications will be made in alignment of the road to protect the cacti. These modifications will not be made if the modifications cause excessive cost or hardship to the oil company.

C. WILDLIFE/VEGETATION/THREATENED & ENDANGERED SPECIES

No Threatened & Endangered species have been identified associated with this project. Therefore, no stipulations have been developed for their protection.

D. CULTURAL RESOURCES

All well sites, and access roads, have had cultural resource surveys completed by a qualified archaeologist or, paleontologist. They have also been cleared through the Phoenix Area Archeologist as required by Sec. 106 of the Historical and Preservation Act.

7.0 UNAVOIDABLE ADVERSE IMPACTS

A. SURFACE ALTERATIONS

None of the adverse impacts listed in 5.0 above can be avoided in a practical manner except those which are mitigated in item 6.0 above and those specified in BLM's 13 point surface use plan.

B. RELATIONSHIP BETWEEN SHORT-TERM USE OF THE ENVIRONMENT VS LONG TERM PRODUCTIVITY.

1. Short Term: (Estimated 20 years) A total loss of production on the land and the associated environmental impacts will continue to influence the surrounding area for the productive life of the well.
2. Long Term: Standard policies provide for rehabilitation of the well sites and access roads. After the land is rehabilitated, it is not expected to return to its original productive capability. Normally, there will be a permanent scar left on the landscape.

C. IRREVERSIBLE AND IRRETRIEVABLE COMMITMENT

Oil and Gas are non-renewable resources, once they have been removed they can never be replaced.

8.0 CUMULATIVE IMPACTS

A. FULL DEVELOPMENT

Each additional well drilled for development increases the soil erosion potential, reduces wildlife habitat and grazing, increases potential soil and geologic pollution resulting from salt loading, reduces the soil's potential to recover, and increases the potential of water pollution from produced waters and hydro-carbons.

measures and recommendations in this document is emphasized to minimize the adverse environmental impacts.

9.0 NEPA COMPLIANCE

A. RESEARCH/DOCUMENTATION

Based on available information, 5-25-95, the proposed location in the following areas of environmental impacts has been cleared:

<u>X</u>	Yes	_____	No	Listed Threatened & Endangered species
<u>X</u>	Yes	_____	No	Critical wildlife habitat
<u>X</u>	Yes	_____	No	Historical and cultural resources

10.0 REMARKS

A. SURFACE PROTECTION/REHABILITATION

All essential surface protection and rehabilitation requirements are specified above.

11.0 RECOMMENDATIONS

A. APPROVAL/DISAPPROVAL

We recommend approval of the proposed action as outlined in item 1.0 above.

6-5-95
Date

Dele A. Humber
Representative - BIA Land
Operations, Uintah and Ouray
Agency

12.0 REVIEWING OFFICIAL

A. CONCURRENCE

We concur with the approval X disapproval _____ of the proposed action as outlined in item 1.0 above.

6/7/95
Date

Allen Shugart
Environmental Coordinator,
Uintah and Ouray Agency

13.0 DECLARATION

A. APPROVAL

It has been determined that the proposed action is not a federal action significantly affecting the quality of the environment as it would require the preparation of an environmental impact statement in accordance with Section 102 (2) (c) of the National Environmental Policy Act of 1969 (42 USC 4331) (2) (C).

6/7/95

Date

Charles H. Cameron
acting Superintendent,
Uintah and Ouray Agency

14.0 CONSULTATION

A. REPRESENTATIVES/ORGANIZATION

Jim Mckunney- Snyder Oil Corporation
Stan Olmstead-BLM
Alvin Ignacio- UTEM
Dale Hanberg- BIA

B:\EASnyd.217

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

FORM APPROVED
Budget Bureau No. 1004-0135
Expires: March 31, 1993

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill or to deepen or reentry a different reservoir.
Use "APPLICATION FOR PERMIT -" for such proposals

SUBMIT IN TRIPLICATE

1. Type of Well

☒ Oil Well ☐ Gas Well ☐ Other

2. Name of Operator

SNYDER OIL CORPORATION

3. Address and Telephone No.

P. O. Box 695, Vernal, UT 84078 801/789-0323

4. Location of Well (Footage, Sec., T., R., m., or Survey Description)

2132' FNL, 1966' FWL NE/SW Sec. 21, T4S, R1E

5. Lease Designation and Serial No.
14-20-H62-4418

6. If Indian, Allottee or Tribe Name

Uintah and Ouray Ute

7. If Unit or CA, Agreement Designation

8. Well Name and No.

Ute Tribal #21-7-F

9. API Well No.

43-047-32191

10. Field and Pool, or Exploratory Area

Unnamed

11. County or Parish, State

Uintah, Utah

12. CHECK APPROPRIATE BOX(s) TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION

☒ Notice of Intent
☐ Subsequent Report
☐ Final Abandonment Notice

TYPE OF ACTION


☐ Abandonment
☐ Recompletion
☐ Plugging Back
☐ Casing Repair
☐ Altering Casing
☒ Other Permit extension

☐ Change of Plans
☐ New Construction
☐ Non-Routine Fracturing
☐ Water Shut-Off
☐ Conversion to Injection
☐ Dispose Water

(Note: Report results of multiple completion on Well Completion or Recompletion Report and Log form.)

13. Describe Proposed or Completed Operations (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)*

Snyder Oil Corporation requests a permit extension until July 10, 1997 to drill the above referenced well.
The permit number is UT080-5M-160.



14. I hereby certify that the foregoing is true and correct

Signed

Lucy Nemer
Lucy Nemer

Title **Senior Clerk**

Date **June 20, 1996**

(This space for Federal or State office use)

Approved by

Title

Conditions of approval, if any:

**Accepted by the
Utah Division of
Oil, Gas and Mining**

FOR RECORD ONLY

Title 18 U.S.C. Section 1001, makes it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

*See Instruction on Reverse Side

7/30/97

United States Department of the Interior



BUREAU OF LAND MANAGEMENT

Vernal District Office
170 South 500 East
Vernal, Utah 84078-2799

Phone: (801) 781-4400


Fax: (801) 781-4410

IN REPLY REFER TO:

3162
UT08438

Snyder Oil Corporation
1625 Broadway, Suite 2200
Denver, CO 80202

July 22, 1997



Re: Notification of Expiration
Well No. Ute Tribal 21-7F
Section 21, T4S, R1E
Lease No. 14-20-H62-4418
Uintah County, Utah

43-047-32691

Gentlemen:

The Application for Permit to Drill the above-referenced well was approved on July 10, 1995. Snyder Oil Corporation requested an extension of the original APD approval for an additional year. The request was reviewed and the extension approved until July 10, 1997. According to our records, no known activity has transpired at the approved location. In view of the foregoing, this office is notifying you the approval of the referenced application has expired. If you intend to drill at this location at a future date, a new Application for Permit to Drill must be submitted.

This office requires a letter confirming that no surface disturbance has been made for this drill site. Any surface disturbance associated with the approved location of this well is to be rehabilitated. A schedule for this rehabilitation must be submitted to this office. Your cooperation in this matter is appreciated.

Sincerely,

Margie Herrmann
Legal Instruments Examiner

cc: State Div. OG&M
Snyder, Vernal Office